Schedule of Rate

Name of Work: Providing, fitting & fixing of Iron door with grill at PG Hostel NIT Silchar. Completion period: 30 days.

OR: CR: OM:

SI. No.	Description of Item	Unit	Quantity	Rate in word	Rate in fig	Amount
1	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	Kg	945.00			
2	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angles 40x40x6 mm for diagonal braces	Sqm	6.00			
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	75.00			

Total = Rs.

Signature of the Agency